No.	Items of work	Per	Quantity
13	Concrete or earthenware pipes for madaboys with necessary works, etc.	No.	9
14	Miscellaneous works such as jungle and site clearing, etc.	Lump	sum.
	Aqueduct of 1 vent 4′×2′ in ¼ mile—		
1	Earthwork excavation	Lump	sum.
2	Burnt brick in surki mortar	C. ft.	997
3	Burnt stone slabs 6″ thick	S. ft.	156
4	Concrete in surki mortar	Sq.	18
5	Plastering with surki mortar	C. yd.	6·00
6	Rough stone work	...	19
7	Turfing	Lump	sum.
	Lifting dam in ⅛ mile—		
1	Earthwork excavation and forming bank	,,	,,
2	Burnt brick in surki mortar	C. ft.	2,472
3	Burnt stone slabs 6″ thick	S. ft.	479
4	Plastering with surki mortar	Sq.	10·00
5	Rough stone work	C. yd.	113
6	Gearing arrangements as per details in the detailed estimate	No.	2
	Constructing a slab drain ⅓ miles—		
1	Earthwork excavation	Lump	sum.
2	Burnt brick in surki mortar	C. ft.	343
3	Burnt stone slabs 6″ thick	S. ft.	139
4	Plastering with surki mortar	Sq.	2·22
	Opening out madaboy channels, Madaboy No. 2—		
1	Earthwork excavation	C. yd.	183
	Madaboy No. 3—		
1	Earthwork excavation	C. yd.	183
	Madaboy No. 8—		
1	Earthwork embankment with forming, etc., complete ...	C. yd.	4·333
2	Turfing	S. yd.	2·110
3	Earthenware pipes	R. ft.	33
	Slabbed drain as per details in channel line Madaboy No. 10 and end grade wall and slabbed tunnel for voni.	Lump	sum.
	Opening out irrigation channel from the sluice of Minor tank of Nidasale village—		
1	Earthwork excavation	C. yd.	908

C. VIJAYARANGAM NAIDU,
Executive Engineer.

SHIMOGA DIVISION.

Dated 10th May 1920.

Notice is hereby given that sealed tenders will be received at the office of the Executive Engineer, Shimoga Division, up to 15th June 1920, for constructing Local Fund Dispensary with In-patient ward at Nyamati. An approximate estimate of quantities is given below. These quantities are not guaranteed. The work should be completed by the end of June 1922.

2. The plans, detailed estimate and conditions may be seen at the Executive Engineer's Office at Shimoga between the hours of 11 A.M. and 5 P.M. on all office days.

3. Tenders should be submitted on printed forms which may be obtained from the Executive Engineer. The tenders should be accompanied by a statement in the form given below, showing the rates at which the different items specified will be executed.

4. Each tender must be accompanied by a deposit of rupees six hundred and fifty-five only (655) in cash or Government Promissory Notes, as earnest money and be superscribed "Tender for constructing Local Fund Dispensary and In-patient ward at Nyamati," in default of which tenders will be rejected.

5. The final acceptance of any tender will rest with the Chief Engineer, who does not bind himself to accept the lowest or any tender or to assign any reason whatever for the rejection of any tender.

6. Within eight days of the acceptance of the tender, the successful competitor will be required to execute the usual contract bond, in default of which, his tender will be considered cancelled, and his earnest money will be forfeited.

7. The name of the successful competitor whose tender has been accepted will be posted on the notice board in the Executive Engineer's Office in due course. No enquiries regarding the acceptance or rejection of a tender will receive any reply.

8. On acceptance of one of the tenders, the earnest money on rejected tenders will be returned.

Abstract estimate for constructing a Dispensary and In-patient ward and Out-houses, etc., at Nyamti.

No.	Items of work	Per	Quantity
1	Earthwork excavation for foundation	C. yd.	150
2	Concrete filling for foundation	C. ft.	1191
3	Stone in chunam for foundation and basement ...	"	3634
4	Burnt brick in mortar superstructure... ...	"	6740
5	Burnt stone slabs 4" to 6" thick nicely dressed ...	S. ft.	881
6	Burnt brick in mortar, arch work	C. ft.	28
7	Cut stone pillars nicely dressed (9"×9"×7')... ...	No.	13
8	Ornamental cut stone brackets	"	4
9	Plastering with chunam	Sqr.	104·17
10	White and colour washing	"	104·17
11	Cement pointing to basement	"	4·94
12	Teakwood work wrought and put up with oiling ...	C. ft.	195·55
13	Do panelled doors complete	S. ft.	330
14	Do battened doors complete	"	23
15	Do windows panelled and glazed shutters with iron bars, etc., complete	"	220
16	Do battened windows complete	"	7
17	Do glazed ventilators complete	"	90
18	Do treble windows with glazed shutters with iron bars, etc., complete	"	32
19	Flooring with 1st class Mangalore tiles 9"×9" on 3" concrete with cement pointing, etc., complete. ...	Sqr.	7·92
20	Flooring with Kadappa slabs over 3" concrete bed with cement pointing, etc., complete	"	10·22
21	Chocolate painting	"	8·60
22	Wood oiling two coats	"	9·85
23	Roofing with 1st class Mangalore tiles on teak reepers, etc., complete	Sqr.	37·00
24	Ornamental ridge tiles set in mortar	R. ft.	90
25	Plain ridge tiles set in mortar	"	64
26	Teakwood ornamental eave board 9" with painting, etc., complete	"	442
27	Do pendents	each	18
28	Do ornamental finials (small)	"	2
29	Do sun shades	"	8
30	Do ornamental finials (big)	"	2
31	Binding wall	R. ft.	147
32	Date stone and fixing charges, etc., complete...	No.	1
33	Clearing the site and levelling ground, etc. ...	L. S.	...
34	Inscription of names, works, etc.	"	...
35	Tarring to wood work	"	...
36	Drainage, etc., complete...	"	...
37	Mangalore ventilating tiles	Each	8
38	Coping with brick in chunam	R. ft.	40
39	Honey Comb Tile work	Sqr.	1·76
40	Zinc sheet for valley	S. ft.	92
41	Teakwood planks for valleys	"	92
42	Burnt stone slabs dressed and fixed 6" thick and well polished and on top and sides for table	S. ft.	31
43	Providing plinth drains and sewage.	L. S.	...